10-AUG-18

FA4417-18-R-0010, CP1018526
Repair Building 90748, 23 SOWS

ADDENDUM #1:

A. Replace specification section 23 09 23 Direct Digital Control System for HVAC with attached specifications revised August 10, 2018.
B. Demolish existing window in room #104 BREAK and install window type B.
    - Sheet D-101, Keynote #25, Change to read, “Demolish window and prep opening for new window assembly.”
    - Sheet A-101, Add window key “B” at window in Break room #104.
    - Sheet A-301, Keynote #14, Change to read, “New window type “B”.
    - Sheet A-603, Keynote #4, Change to read, “New window type “B”.
C. Add 12” to west edge of concrete landing and aluminum canopy at door #01 for a 6’-0” wide entry stoop. Walk-off grate size can remain but location must center on door opening.
    - Sheet A-101, Detail #1/A-101, Change 5’-0” dimension to read 6’-0”.
    - Sheet A-102, Change 5’-0” LANDING dimension to read 6’-0” LANDING.
D. Delete 4” drain and pipe from walk-off grate to storm inlet.”
    - Sheet A-101, Keynote #5; Sheet A-301, Keynote #28; & Sheet A-603, Detail #2/A-603, Delete note “Provide 4” drain and 4” PVC drain pipe… to existing storm inlet.”
E. Sheet A-401, Room Finish Schedule, Room #114 STANEVAL and Room #119 OPS FLOOR, Change Ceiling Height from 9’-0” to read 10’-0”.

END OF ADDENDUM