

BID SCHEDULE

NOTE: BIDS shall include sales tax and all other applicable taxes and fees.

This is a LUMP SUM BID. The following Bid Schedule is intended as a general recap of the work involved, it is NOT an all-inclusive detail of everything required to do this job. It is the contractor's responsibility to carefully review the plans, specifications, and project to determine what is needed to do the whole job, and to reflect this in his LUMP SUM BID. This basis of award will be the total base bid for the project. IF DURING THE BID PROCESS, THE CONTRACTOR NOTICES A DISCREPANCY BETWEEN THE WORK REQUIRED AND THIS BID SCHEDULE HE MUST BRING IT TO THE ENGINEER'S ATTENTION BEFORE THE BID DATE.

CHOCTAW BEACH FIRE STATION BID SCHEDULE					
NO.	ITEM	QUANTITY	UNITS	UNIT PRICE	TOTAL PRICE
Roadway - Typical					
1.	220 LB/SY SP-12.5 ASPHALT	205	TN		
2.	165 LB/SY SP-12.5 ASPHALT	62	TN		
3.	8" LIMEROCK BASE (LBR-100)	3050	SY		
4.	12" SANDCLAY STABILIZED SUBGRADE (LBR-70)	3603	SY		
5.	6" THICK 4000 PSI CONCRETE PAD W/ 6-6-10 WIRE MESH W/ SAWCUT JOINTS	393	SY		
6.	TYPE CR-E CURB RAMP W/ DETECTABLE WARNINGS	2	EA		
7.	5-FT WIDE CONCRETE SIDEWALK, 4" THICK	161	SY		
Stormwater					
8.	FDOT INDEX 425-010 TYPE "P8" MANHOLE	1	EA		
9.	FDOT INDEX 425-052 TYPE "C" INLET	4	EA		
10.	12" ADS N-12 HDPE INSTALLED	144	LF		
11.	15" RCP INSTALLED	236	LF		
12.	15" FDOT INDEX 430-021 M.E.S.	2	EA		
13.	18" THICK ALABAMA CLASS II RIP RAP OVER D-2 FILTER FABRIC	95	SY		
14.	FDOT MODIFIED TYPE F CURB	1245	LF		
Miscellaneous					
15.	LAYOUT	1	LS		
16.	SODDING	7000	SY		
17.	SEED AND MULCH	1500	SY		

CHOCTAW BEACH FIRE STATION BID SCHEDULE					
NO.	ITEM	QUANTITY	UNITS	UNIT PRICE	TOTAL PRICE
18.	THERMO, STD, WHITE, SOLID, 4", PARKING	320	LF		
19.	THERMO, STD, WHITE, SOLID, 24" STOP LINE	21	LF		
20.	CLEARING & GRUBBING (SELECT TREE REMOVAL)	1	LS		
21.	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	3	AS		
22.	EROSION CONTROL / SILT FENCE	1000	LF		
23.	LANDSCAPE	1	LS		
Building					
24.	FIRE STATION BUILDING, FINISHED	1	LS		
Utilities					
25.	SEPTIC TANK & DRAINFIELD	1	LS		
26.	90kW GENERATOR W/ ATS, WIRING, ENCLOSURE	1	LS		
General					
27.	MAINTENANCE OF TRAFFIC	1	LS		
28.	BONDS (MAX 2% OF BID)	1	LS		
29.	MOBILIZATION (MAX 5% OF BID)	1	LS		
Total Lump Sum					

NOTE: The unit prices listed above will be used as the basis for computing the value of any change orders either additive or deductive. **THE OWNER RESERVES THE RIGHT TO REJECT ANY OR ALL BIDS.**