

Date: 22 February 2023

To: CMSgt. William Hall

Subject: ADDENDUM NO. 1

Project: RENOVATE EXTERIOR – BUILDING 1109

Job #: ANG# FAKZ162109
SSL# 18078

From: David Donovan

The Specifications for the Renovate Exterior – Building 1109 (FAKZ162109), dated 1 June 2021 are amended as follows. (Where there are conflicts between the plans and specifications and the addendum, this addendum shall govern).

Item No. 1: Refer to specification section 01 3000 “Administrative Requirements.” Delete paragraph 3.10(A)3 and replace it with the following:

3. Issuing Office DoDAAC: F6L321D

Item No. 2: Refer to specification section 05 4000 “Cold Formed Metal Framing.” Delete paragraph 3.02(B) and replace it with the following:

B. Align floor and ceiling tracks; locate to wall layout. Secure in place with fasteners at maximum 16 inches (406mm) on center. Coordinate installation of sealant with floor and ceiling tracks.

Item No. 3: Refer to specification section 07 4300 “Aluminum Faced Composite Wall Panels.” Delete paragraph 2.04(B)1 and replace it with the following:

1. Thickness: 0.5mm (0.020”)

Item No. 4: Refer to specification section 07 5600 “Fluid Applied Roofing.” -

- Reference paragraph 1.07(E)1. Replace reference to “Owner” with “the Government.”
- Reference paragraph 1.07(H)1. Delete “including owner’s insurance representative”

Item No. 5: Refer to specification section 07 7100 “Roof Specialties.” Add the following as paragraph 3.05(C)2:

2. Coordinate cast iron boots specified in section 05 500 and storm drainage specified in section 33 4112.

- Item No. 6:** Refer to specification section 08 8000 “Glazing.” Delete paragraph 2.01(A)2(b), 2.01(A)2(c), and 2.01(A)2(d) and replace them with the following:
- b.** Winter U-Value: 0.23
 - c.** Solar Heat Gain Coefficient: 0.21
 - d.** VLT (%): 46
- Item No. 7:** Refer to specification section 10 1400 “Signage.” Delete paragraph 2.01(A)1(e)
- Item No. 8:** Refer to specification section 01 4000 “Quality Requirements.” Delete paragraph 1.05(D).
- Item No. 9:** Refer to specification section 00 0102 “Project Information and Summary.” Delete paragraph 1.02(A) and replace it with the following:
- A. 270 calendar days from notice to proceed to Beneficial Occupancy. The listed duration shall include completion of all punch list activities identified at the project final inspection. The Government intends to continue occupying the building for the duration of the project.
- Item No. 10:** Refer to specification section 01 5000 “Temporary Facilities and Controls.” Delete paragraph 1.01(H). Delete paragraph 1.09.

End of Addendum #1