

## BID SCHEDULE

NOTE: BIDS shall include sales tax and all other applicable taxes and fees.

This is a LUMP SUM BID. The following Bid Schedule is intended as a general recap of the work involved, it is NOT an all-inclusive detail of everything required to do this job. It is the contractor's responsibility to carefully review the plans, specifications, and project to determine what is needed to do the whole job and to reflect this in his LUMP SUM BID. This basis of award will be the total base bid for the project. IF DURING THE BID PROCESS, THE CONTRACTOR NOTICES A DISCREPANCY BETWEEN THE WORK REQUIRED AND THIS BID SCHEDULE HE MUST BRING IT TO THE ENGINEER'S ATTENTION BEFORE THE BID DATE.

FDOT ITEM NO.	NO.	ITEM	QUANTITY	UNITS	UNIT PRICE	TOTAL
0101 01	1.	Mobilization (5%)	1	LS		
0110 1 1	2.	Demolition, Clearing and Grubbing, Site Cleanup (3%)	1	LS		
0102 1	3.	Maintenance of Traffic	1	LS		
	4.	Erosion Control	1	LS		
0120 1	5.	*Regular Excavation	2,797	CY		
0120 6	6.	*Regular Embankment (Fill)	3,101	CY		
0522 1	7.	4" concrete (sidewalk, flume, spillway)	135	SY		
0522 2	8.	6" concrete (sidewalk)	386	SY		
0527 2	9.	Detectable Warning	67	SF		
0542 70	10.	Concrete Wheel Stop	204	EA		
0711 15101	11.	6" white solid striping (thermoplastic)	0.81	GM		
0711 11421	12.	6" blue solid striping (thermoplastic)	376	LF		
0711 11123	13.	12" Crosswalk Stripe	119	LF		
71111125	14.	24" Stop Bar/ Crosswalk	180	LF		
0711 11160	15.	Handicap symbol	9	EA		
0711 14170	16.	Preformed White Directional Arrows	42	EA		
0700 1 11	17.	Site Single Post Sign w/Panel Less Than 12 sf (excludes ADA signage)	11	EA		
0700 1 11	18.	ADA Single Post Sign w/Panel Less Than 12 sf	9	EA		
	19.	4' black fence	1	LS		
327 70 16	20.	0.5" Milling	382	SY		
334113	21.	2" Asphalt SP 9.5	1,174	TN		
285704	22.	6" Limerock Base (OBG 4)	7,571	SY		
5152311	23.	6" graded aggregate Base (OBG 4)	2,994	SY		
5152311	24.	Aluminum Pedestrian Railing w/Picket Infill	604	LF		
0530 3 4	25.	Riprap	35	TN		
	26.	18" Curb and Gutter	4,128	LF		
	27.	18" Valley Curb	24	LF		
425121	28.	Type C (modified - outfall structure) (includes additional concrete for stabilization and debris grate)	3	EA		
4251561	29.	Type F DBI	5	EA		
4252241	30.	Storm Manhole	2	EA		
430982121	31.	12" Mitered End Section	1	EA		

FDOT ITEM NO.	NO.	ITEM	QUANTITY	UNITS	UNIT PRICE	TOTAL
430982125	32.	18" Mitered End Section	3	EA		
430982129	33.	24" Mitered End Section	1	EA		
	34.	Existing Pond 1 Bold and Gold Filtration System	1	LS		
	35.	Proposed Pond 2 Bold and Gold Filtration System	1	LS		
430175112	36.	12" HDPE Storm Pipe	35	LF		
430175118	37.	18" RCP Storm Pipe	58	LF		
430175118	38.	18" HDPE Storm Pipe	205	LF		
430175124	39.	24" HDPE Storm Pipe	103	LF		
1050 31206	40.	6" PVC (Sanitary Sewer)	206	LF		
	41.	1.25" water service	54	LF		
1050 41202	42.	2" Water service	443	LF		
	43.	8" fire line	22	LF		
	44.	Hydrant	1	EA		
	45.	2" backflow (RPZ)	1	LS		
	46.	2" water meter	1	EA		
	47.	1.25" ball valve	1	EA		
	48.	2" ball valve	1	EA		
	49.	Electric vehicle charging stations 2 dual chargers plus install	1	LS		
	50.	Grinder Lift Station	1	LS		
	51.	Civil Structural - ADA ramp, Shower plaza walls and stairs, pedestrian railing	1	LS		
	52.	Transit Facility building	1	LS		
	53.	Storage building	1	LS		
	54.	Site lighting	1	LS		
	55.	Landscaping and irrigation system (including well and permits)	1	LS		
		<b>TOTAL LUMP SUM</b>				

NOTE: The unit prices listed above will be used as the basis for computing the value of any change orders either additive or deductive. **THE OWNER RESERVES THE RIGHT TO REJECT ANY OR ALL BIDS.**