

BID SCHEDULE

NOTE: BIDS shall include sales tax and all other applicable taxes and fees.

This is a LUMP SUM BID. The following Bid Schedule is intended as a general recap of the work involved, it is NOT an all-inclusive detail of everything required to do this job. It is the contractor's responsibility to carefully review the plans, specifications, and project to determine what is needed to do the whole job, and to reflect this in his LUMP SUM BID. This basis of award will be the total base bid for the project. IF DURING THE BID PROCESS, THE CONTRACTOR NOTICES A DISCREPANCY BETWEEN THE WORK REQUIRED AND THIS BID SCHEDULE HE MUST BRING IT TO THE ENGINEER'S ATTENTION BEFORE THE BID DATE.

PAY ITEM NO.	ITEM	QTY	UNITS	UNIT PRICE	TOTAL PRICE
ROADWAY - TYPICAL					
1	220 LB/SY SP-12.5 ASPHALT	269	TN		
2	165 LB/SY SP-12.5 ASPHALT	68	TN		
3	8" LIMEROCK BASE (LBR-100)	3915	SY		
4	12" SANDCLAY STABILIZED SUBGRADE (LBR-70)	3915	SY		
5	6" THICK 4000 PSI CONCRETE PAD W/ 6-6-10 WIRE MESH W/ SAWCUT JOINTS	456	SY		
6	TYPE CR-E CURB RAMP W/ DETECTABLE WARNINGS	1	EA		
7	TYPE CR-C CURB RAMP W/ DETECTABLE WARNINGS	1	EA		
8	5-FT WIDE CONCRETE SIDEWALK, 4" THICK	183	SY		
STORMWATER					
9	FDOT INDEX 425-052 TYPE "E" INLET	1	EA		
10	FDOT INDEX 425-052 TYPE "C" INLET	8	EA		
11	18" ADS N-12 HDPE INSTALLED	657	LF		
12	24" ADS N-12 HDPE INSTALLED	72	LF		
13	24" FDOT INDEX 430-021 M.E.S.	1	EA		
14	18" THICK ALABAMA CLASS II RIP RAP OVER D-2 FILTER FABRIC	25	SY		
15	CONCRETE WEIR 4" THICK 3000 PSI CONCRETE	1	LS		
16	CONCRETE PAD FOR 5,000 GAL WATER STORAGE TANK (SEE DETAIL IN SPECS APPENDIX)	1	LS		
17	FDOT MODIFIED TYPE F CURB	1800	LF		
MISCELLANEOUS					
18	LAYOUT	1	LS		
19	EARTHWORK	1	LS		
20	SODDING	12,300	SY		
21	SEED AND MULCH	19000	SY		
22	THERMO, STD, WHITE, SOLID, 6", PARKING	340	LF		
23	DOUBLE 6" YELLOW THERMO STRIPING, ENTRANCE	300	LF		
24	THERMO, STD, WHITE, SOLID, 24" STOP LINE	75	LF		
25	DUMPSTER ENCLOSURE	1	LS		
26	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	4	AS		
27	GRAVEL CONSTRUCTION ENTRANCE / SEDIMENT CONTROL	160	SY		
28	EROSION CONTROL / SILT FENCE	1500	LF		

29	ALUMINUM FLAG POLE 30-FT (INCLUDES FOUNDATION)	1	EA		
30	LANDSCAPE (IRRIGATION PLAN SUPPLIED & INSTALLED BY CONTRACTOR)	1	LS		
BUILDING					
31	PEMB FIRE STATION BUILDING, FINISHED (INCLUDES FIRE SUPPRESSION SYSTEM DESIGNED BY OTHERS)	1	LS		
UTILITIES					
32	WATER SERVICE FOR BUILDING, WATER LINE TO STORAGE TANK, PLUMBING, SEPTIC TANK & DRAINFIELD	1	LS		
33	UNDERGROUND PROPANE TANK INSTALL & FUEL GAS CONNECTION (TANK SUPPLIED BY OWNER)	1	LS		
34	90kW GENERATOR W/ ATS, WIRING, ENCLOSURE (OR EQUAL)	1	LS		
GENERAL					
35	MAINTENANCE OF TRAFFIC	1	LS		
36	BONDS (MAX 2% OF BID)	1	LS		
37	MOBILIZATION (MAX 5% OF BID)	1	LS		
TOTAL CONSTRUCTION COST					
Total Lump Sum					

NOTE: The unit prices listed above will be used as the basis for computing the value of any change orders either additive or deductive. **THE OWNER RESERVES THE RIGHT TO REJECT ANY OR ALL BIDS.**

