

**ATTACHMENT G
BID FORM**

BID SUMMARY - PART A: FIRE STATION BUILDING (FC #M0021)				
Item No.	Description	Unit	Quantity	Bid Amount
1	Architectural, Structural, Plumbing, Electrical, Fire Protection, HVAC	LS	1	\$
2	Civil (See Civil Pay Item Summary Below - Insert Civil Base Bid Total Here)	LS	1	\$
3	Low Voltage Design - Allowance for design, furnishing and installation of low voltage systems including voice, cable TV, data, and Wi-Fi cabling, also door access control system and IP security camera system. (100% of allowance amount shall go to low voltage subconsultants direct cost and shall not be used for general contractor's markup or overhead cost)	LS	1	\$ 25,000.00
4	Contingency - To Be Used Only Upon Approval by the Project Owner	LS	1	\$ 50,000.00
TOTAL BASE BID - PART A				\$

CIVIL BASE BID PAY ITEMS - FIRE STATION BUILDING (FC #M0021)				
Item No.	Description	Unit	Quantity	Bid Amount
1	Mobilization	LS	1.0	\$
2	Erosion and Sedimentation Control	LS	1.0	\$
3	Demolition of Existing Building and Concrete (includes disconnection of all utilities)	LS	1.0	\$
4	Clearing and Grubbing (0.30 Ac.)	LS	1.0	\$
5	Site Excavation, Plan Quantity Only	CY	1,000.0	\$
6	Borrow Fill, Truck Measure Only	CY	720.0	\$

C-410

7	Removal of Unsuitable Material (per Geotechnical Report)	CY	10.0	\$
8	#57 Bedding Stone, 4" Thick	SY	450.0	\$
9	Reinforced Concrete Pavement, 6" Thick	SY	300.0	\$
10	Reinforced Concrete Pavement, 6" Thick (Apparatus Bay Approach Slab)	SY	150.0	\$
11	Concrete Sidewalk, 4" Thick (with fiber reinforcement)	SY	190.0	\$
12	Concrete Utility Pad (with fiber reinforcement)	SY	20.0	\$
13	Sod	SY	1,000.0	\$
14	Pavement Striping (Thermoplastic)	LS	1.0	\$
15	Single Post Sign	AS	1.0	\$
16	8"x6" Water Main Live Tap	LS	2.0	\$
17	6" PVC WM, C900, DR14 Pipe	LF	20.0	\$
18	2" HDPE PE4710 (SDR 9) Water Service	LF	51.0	\$
19	6" DDCA with Fire Department Connection with Check Valve and Insulated Fiberglass Enclosure	EA	1.0	\$
20	Fire Hydrant Assembly	EA	1.0	\$
21	6" Fire Main, DR18 Pipe	LF	71.0	\$
22	Potable Water Meter, 2" Pipe	EA	1.0	\$
23	Backflow Preventer, RPZ, 2" Pipe	EA	1.0	\$
24	6"x6"x2" Tee with 2" Curb Stop	EA	1.0	\$
25	Sewer Connection to Existing Sewer Main	LS	1.0	\$
26	Sewer Cleanout Assembly, 4" Diameter	EA	3.0	\$
27	PVC Sewer Lateral, 4" Diameter	LF	82.0	\$
28	Oil/Water Separator	EA	1.0	\$
29	Relocation of Existing Propane Tanks (2 Tanks)	LS	1.0	\$
Civil - Base Bid Total				

BID SUMMARY - PART B: TOWN HALL BACK UP POWER (HMGP #4399-073-R)				
Item No.	Description	Unit	Quantity	Bid Amount
1	All work associated with providing backup power to Town Hall beginning at the Emergency Generator including furnishing and installing conduit, conductor wire, electric meter, auto-transfer switch, panel, annunciator, disconnect and etc. for a complete and operational system.	LS	1	
TOTAL BASE BID - PART B				\$

BID SUMMARY - PART C: FIRE STATION GENERATOR (FC#M0138 / HMGP #4399-043-R)				
Item No.	Description	Unit	Quantity	Bid Amount
1	All work associated with providing electric power and backup power to fire station including furnishing and installing 125KW Diesel powered generator with wind debris rated enclosure, base fuel tank, transfer switch, electric meter, auto-transfer switch, annunciator, disconnect, power relocation, fire alarm control panel, CT Cabinet, Panel MP, conduit, wire, fire alarm tamper switch, etc. complete and operational system. Include a \$12,000 allowance for electric utility charges by Florida Public Utilities.	LS	1	
TOTAL BASE BID - PART C				\$