

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
BASE BID					
1	General Provisions	1	LS		
2	Maintenance of Traffic	1	LS		
3	Clearing, Grubbing, Demolitions, Removals, etc.(to include removal of existing concrete, asphalt, curb and gutter, brick pavers, pull box, backflow preventor, signs, shower station, trees, posts, cables, wood deck, stairs, and CMU wall as shown on the plans and required by the specifications to include the cost of transport and disposal for the lump sum amount of)	1	LS		
4	Earthwork	1	LS		
5	Restroom Facility (to include all mechanical, plumbing, and building electrical extending to 5 feet outside the building)	1	LS		
6	Irrigation System (furnish and install all fittings, controllers, piping, pipe sleeves, sprinkler heads, valves, sensors, well, control panel, backflow preventors, and other as required by the plans and specifications complete and in place for)	1	LS		
7	Electrical (furnish and install all electrical from FPL transformer to building service entrance and all interior and exterior electrical components including exterior lighting and concrete bases complete and in place for the lump sum amount of)	1	LS		
8	Site Lighting	1	LS		
9	ADS Storm Chambers	1	LS		
10	Ramp and Stairs at Pavillion	61	LF		
11	Dune Crossover	105	LF		
12	Weardeck Boardwalk (furnish and install boardwalk complete with all piles, stringers, beams, joists, plates, blocking, rails, stairs, posts, mesh infill, composite decking and top rails, stainless steel bolts, screws, and fasteners, aluminum handrail, shower grates and other as required by the plans and specifications complete and in place for)	585	SF		
13	Type SP-12.5 Asphalt, 1.5" Depth	1,800	SY		
14	Prime Coat	1,800	SY		
15	Final Grading and Seal Rolling Prior to Paving	1,800	SY		
16	Graded Crushed Aggregate Base Course, 6" Depth, Min. CBR 100	1,800	SY		
17	Stabilized Subgrade, LBR 40, 12" Depth	1,800	SY		
18	Stabilized Subgrade LBR 40, 12" Depth Upgrade to White Sand (to be used if existing soil conditions are not complaint with City of Destin white sand requirements)	654	CY		

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
19	Removal of Non-Compliant Sand (to be used if existing soil conditions are not complaint with City of Destin white sand requirements)	1,123	CY		
20	Geogrid Permeable Plastic Pavement (furnish and install geogrid complete with geomembrane, permeable plastic pavement, gravel, and aggregate surface course, and other as required by the plans and specifications complete and in place for the lump sum price of)	1	LS		
21	Thermoplastic White High Intensity Pedestrian Crosswalk	60	LF		
22	Thermoplastic Stop Bar	30	LF		
23	Thermoplastic Directional Arrow, Single Head (Straight Ahead) 12sf	11	EA		
24	Thermoplastic Directional Arrow, Single Head (Turn Left/Right)	2	EA		
25	Thermoplastic Solid 6", White	750	LF		
26	Thermoplastic Handicap Parking Space with Symbol	1	EA		
27	Thermoplastic Symbol, LVS Only (every third space)	10	EA		
28	Bollards	28	EA		
29	Post Mounted Signs	15	EA		
30	1' Ribbon Curb, Per County Detail	270	LF		
31	Fiber Reinforced Concrete Sidewalk	432	SY		
32	Detectable Handicap Warning Mat, FDOT Index 304	162	SF		
33	Ditch Bottom Inlet, Type C, 6'-12' depth	4	EA		
34	15" RCP Pipe	168	LF		
35	Storm Manhole with weep hole, Type 8, 6-12 ft deep	2	EA		
36	Sewer Lateral and Connections (to include all piping fittings, etc. as required for new facility)	1	LS		
37	Water service (to include all piping, fittings, installation, backflow preventer, meter, etc. as required for new facility and any necessary relocations/repairs for the existing facility water service)	1	LS		
38	MDF Public Shower with Foot Wash	3	EA		
39	MDF Water Fountain and Bottle Filler	1	EA		
40	Fire Extinguishers and Cabinet	2	EA		
41	Silt Fence, Type IV	1,400	LF		
42	Temporary Gravel Construction Entrance	172	SY		
43	Synthetic Erosion Control Wattles	20	LF		
44	Concrete Bumper Guard	19	EA		
45	Bike Rack (5 Bikes)	2	EA		
46	Palm Trees, Sabal Palms	78	EA		

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
47	Shrubs - Callistemon Viminalis (CD) Red Bottlebrush	34	EA		
48	Shrubs - Callistemon Viminalis (CV) Weeping Bottlebrush	45	EA		
49	Shrubs - Nerium Oleander (NO)	34	EA		
50	Shrubs - Serenoa Repens (SR)	28	EA		
51	Shrubs - Zamia Floridana (ZP)	21	EA		
52	Shrubs - Lomandra Breeze (LB)	54	EA		
53	Shrubs - Miscanthus Sinensis (MS)	23	EA		
54	Ground Cover - Rosa x Meidrifora (RM)	20	EA		
55	Dune Mix Planting Area (DM)	712	SF		
56	Sod Planting Area	1,872	SF		
57	Utility Allowance (utility allowance is provided for contractor to pay service and connection fees to various utilities (FPL, DWU, etc.). Contractor to be reimbursed at cost based on paid receipts to the various utilities. Utility allowance will be adjusted up or down based on actual paid receipts.)	1	LS	\$15,000.00	
BASE BID TOTAL:					
ADDITIVE ALTERNATE 1: Removal of Boardwalk at Tarpon Beach Access and Addition of Sidewalk					
58	Maintenance of Traffic	1	LS		
59	Removal of Existing Boardwalk	1,090	SF		
60	Silt Fence, Type IV	130	LF		
61	Fiber Reinforced Concrete Sidewalk	80	SY		
62	White Sand Fill	40	CY		
63	Dune Mix Planting Area (DM)	432	SF		
ADDITIVE ALTERNATE 1 TOTAL:					
TOTAL:					

BID AMOUNT IN WORDS: _____

ARTICLE 6- TIME OF COMPLETION

6.01 BIDDER agrees that the Work will be substantially complete within 200 calendar days after the date when the Contract Times commence to run as provided in Paragraph 4.01 of the General Conditions, and will be completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions within 230 calendar days after the date when the Contract Times commence to run.

A. Parts of the Work shall be substantially completed on or before the following Milestone:

1. Milestone 1: If the bid alternate is awarded the existing boardwalk at Tarpon Beach must be removed within 60 days of the NTP.
2. Milestone 2: The dune walkover must be fully constructed before turtle season starts on May 01, 2027.