BID

Proposal of _____,
(BIDDER)

organized and existing under the laws of the State of _____

and doing business as _____.
(insert "a corporation", "a partnership", or "an individual" as appropriate)

To City of Fayette, 59 Medgar Evers Blvd, Fayette, MS 39069.
(OWNER)

In compliance with the Advertisement for Bids, BIDDER hereby proposes to perform all WORK for the construction of Municipal Safety Complex

_____

in strict accordance with the CONTRACT DOCUMENTS, within the time set forth therein, and at the prices stated below.

By submission of this BID, the BIDDER certifies, and in the case of a joint BID each party thereto certifies as to its own organization to the following:

1. That this BID has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this BID with any other BIDDER or with any competitor.

2. The BIDDER is familiar with all laws and regulations that may affect cost, progress, and performance of the work.

BIDDER hereby agrees to commence WORK under this contract on or before a date to be specified in the NOTICE TO PROCEED and to fully complete the PROJECT within **240** consecutive calendar days thereafter.

BIDDER further agrees to pay to the Owner as liquidated damages the sum of $250 for each calendar day of delay thereafter as outlined in the Agreement.

BIDDER acknowledges receipt of the following ADDENDA, dated:

_____

_____

_____

It is understood that the quantities of work shown in the Proposal are approximate and are subject to increase or decrease, and that the undersigned will perform the work at the unit prices indicated in the Proposal whether the quantities are increased or decreased.

NOTE: BIDS shall include sales tax and all other applicable taxes and fees.

BIDDER agrees to perform all the work described in the CONTRACT DOCUMENTS for the following unit prices:

March 25, 2025

BID FORM

CITY OF FAYETTE
MUNICIPAL SAFETY COMPLEX

BASE BID

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENSION
Greenberg Boulevard, Municipal Safety Complex Building, Driveway, and Sitework					
1	Mobilization, Demobilization	LS	1	XXXXXXX	
2	Erosion Control (Silt Fence, Wattles, and Related Items)	LS	1	XXXXXXX	
3	Clearing & Grubbing	AC	7.60		
4	Permanent Erosion Control Mat	SY	410		
5	Degradable Erosion Control Mat (Type B)	SY	5,675		
6	Concrete Block Erosion Mat	SY	135		
7	Seeding, Fertilizer & Mulch	AC	1.25		
8	Undercut Excavation, (FM)	CY	4,000		
9	Excess Excavation, (FM)	CY	4,335		
10	Borrow Excavation, Contractor Furnished (FM)	CY	5,220		
11	Unclassified Excavation (FM)	CY	660		
12	Lime Treated Subgrade, 12", (PM)	SY	4,415		
13	Granular Surface (No. 610 Limestone) (PM)	TN	510		
14	Granular Base (No. 610 Limestone) (PM)	TN	825		
15	Granular Shoulder (LVM)	CY	220		
16	Heavy-Duty Concrete Pavement (8") (PM)	SY	166		
17	Light-Duty Concrete Pavement (5") (PM)	SY	88		
18	Concrete Sidewalk (PM)	SY	182		
19	Striping, Signage, and Concrete Parking Stops	LS	1	XXXXXXX	
20	Storm Drainage	LS	1	XXXXXXX	
21	Municipal Safety Complex Building & Foundation, Complete	LS	1	XXXXXXX	
22	Security, Access Control, Data & Networking	ALLOW	1	10,000.00	10,000.00
23	Building Signage	ALLOW	1	5,000.00	5,000.00
24	Landscaping	ALLOW	1	5,000.00	5,000.00
25	Domestic Water Service	LS	1	XXXXXXX	
26	Sanitary Sewer Service	LS	1	XXXXXXX	
27	Materials Testing	ALLOW	1	25,000.00	25,000.00
28	Project Sign	EA	1	XXXXXXX	
				TOTAL BASE BID	

ALTERNATE #1

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENSION
Municipal Safety Complex Meeting Room Building and Sitework					
A1-1	Undercut Excavation, (FM)	CY	320		
A1-2	Borrow Excavation, Contractor Furnished (FM)	CY	320		
A1-3	Concrete Sidewalk (PM)	SY	121		
A1-4	Municipal Safety Complex Meeting Room Building & Foundation, Complete	LS	1	XXXXXXX	
A1-5	Materials Testing	ALLOW	1	7,500.00	7,500.00
				TOTAL ALTERNATE #1 BID	

ALTERNATE #2

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENSION
Greenberg Boulevard, Municipal Safety Complex Driveway, and Site Surfacing					
A2-1	Granular Surface (No. 610 Limestone) (PM) [DEDUCT FROM BASE BID]	TN	-510		
A2-2	Heavy-Duty Concrete Pavement (8" thick) (PM)	SY	515		
A2-3	Light-Duty Concrete Pavement (5" thick) (PM)	SY	1225		
A2-4	Hot Mix Asphalt Base Course, ST 19 mm	TN	355		
A2-5	Hot Mix Asphalt Base Course, MT 19 mm	TN	345		
A2-6	Hot Mix Asphalt Binder Course, MT 12.5 mm	TN	225		
A2-7	Hot Mix Asphalt Surface Course, ST 9.5 mm	TN	165		
A2-8	Granular Shoulder (LVM)	CY	70		
A2-9	Striping & Signage	LS	1	XXXXXXX	
A2-10	Materials Testing	ALLOW	1	5,000.00	5,000.00
				TOTAL ALTERNATE #2 BID	

ALTERNATE #3

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENSION
East and South Parking Sitework					
A3-1	Clearing & Grubbing	AC	0.20		
A3-2	Undercut Excavation, (FM)	CY	660		
A3-3	Excess Excavation, (FM)	CY	360		
A3-4	Borrow Excavation, Contractor Furnished (FM)	CY	975		
A3-5	Lime Treated Subgrade, 12" Depth, (PM)	SY	846		
A3-6	Degradable Erosion Control Mat (Type B)	SY	564		
A3-7	Seeding & Fertilizing	AC	0.25		
A3-8	Light-Duty Concrete Pavement (5" thick) (PM)	SY	747		
A3-9	Granular Shoulder (LVM)	CY	8		
A3-10	Striping & Signage	LS	1	XXXXXXX	
A3-11	Materials Testing	ALLOW	1	6,000.00	6,000.00
				TOTAL ALTERNATE #3 BID	

TOTAL BID (BASE BID + ALT #1 + ALT #2 + ALT #3)

Respectfully submitted:

(Signature)	(Date)
(Title)	(License number)

(Address)

SEAL - (if BID is by a corporation)